BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/01/2015-16, Date:04.01.2016 **Indent No.20423**

SCHEDULE-B

NAME OF WORK: Construction of Culverts at AYR layout in W.no.12 Shetty halli Sub division

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor **M/S.Inchara Construction**		
				In Figures (Rs.)	In Words (Rs.)	Cont. AMOUNT
1	2	3	4	5	6	7
1	Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods complete as per specfication & as per direction of Engineer-in-charge	Cum	95.04	107.35	Rupees One Hundred Seven and Thirty Five Paise Only	10202.54
2	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.86cum and fine aggregate @ 0.58cum machine mixed, concrete laid in layers not exceeding 15cms. Thick, well compacted, in foundation and plinth, cost of all materials, labour, HOM of machinery, curing complete as per specfication & as per direction of Engineer-in-charge	Cum	11.88	4710.58	Rupees Four Thousand Seven Hundred Ten and Fifty Eight Paise Only	55961.69
3	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregate @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15cms. Thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specfication & as per direction of Engineer-in-charge	Cum	42.77	5020.61	Rupees Five Thousand Twenty and Sixty One Paise Only	214731.49

Signature of the Contractor

For INCHARA CONSTRUCTIONS

Proprietor

Executive Engineer

4	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1:5:3) for raft foundation, column footing, main and secondary beams. complete as per specfication & as per direction of Engineer-in-charge	Cum	16.39	5882.46	Rupees Five Thousand Eight Hundred Eighty Two and Forty Six Paise Only	96413.52
5	Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Tonne	2.02	64875.14	Rupees Sixty Four Thousand Eight Hundred Seventy Five and Fourteen Paise Only	131047.78
6	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications.	Sqm	124.56	284.94	Rupees Two Hundred Eighty Four and Ninety Four Paise Only	35492.13
7	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a)Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b)Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c)Add loading and unloading complete as per specfication & as per direction of Engineer-in-charge	Cum	95.04	67.54	Rupees Sixty Seven and Fifty Four Paise Only	6419.00
					Total	550268.15
					Percentage	-7.09%

Signature of the Contractor

For INCHARA CONSTRUCTIONS

Proprietor

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor

Executive Engineer